
## IDLE SPEED INSPECTION

EM1KZ-01


## 1. INITIAL CONDITIONS

- (a) Engine at normal operating temperature
- (b) Air cleaner installed
- (c) All pipes and hoses of air induction system connected
- (d) All vacuum lines properly connected
- (e) EFI system wiring connectors fully plugged
- (f) All operating accessories switched OFF
- (g) Ignition timing check correctly
- (h) Transmission in neutral position
- (i) Air conditioning switched OFF



## 2. When using hand-held tester: CONNECT HAND-HELD TESTER

- (a) Connect a hand-held tester to the DLC3.
- (b) Please refer to the hand-held tester operator's manual for further details.



## 3. When not using hand-held tester: CONNECT TACHOMETER

Connect tachometer test probe to terminal  $IG \ominus$  of the check connector.

- 4. INSPECT IDLE SPEED
- (a) Race the engine at 2,500 rpm for approx. 90 seconds.
- (b) Check the idle speed.

Idle speed (w/ Cooling fan OFF): 750 ± 50 rpm

If the idle speed is not as specified, check the air intake system.

- 5. When using hand-held tester: DISCONNECT HAND-HELD TESTER
- 6. When not using hand-held tester: DISCONNECT TACHOMETER